



PRV INSPECTION AND TEST REPORT

BRANCH: Fort St John

UVL ID#: 2288F

Work Order: 307575

Customer PO#:

Customer CANADIAN NATURAL RESOURCES LIMITED
Facility: LADYFERN
A#: A133291
Cust. Ref.:
Cust. WO#:

LSD: a-084-G/94-H-01
Vessel SN:
Valve PO:
Cust AFE#:

Date: 08/22/2011
PSV Location: ABSORBER
Cust Id: PSV-610
PO LINE#:
Cost Centre#: 31302000

VALVE DATA

Man.: ANDERSON GREENWC **Model:** 44314F152/S1/NACE **Serial:** 01/40828 **Seat:** POP
Conn. Flanged **Inlet:** 1.5" 900 RF **Orifice:** F **Outlet:** 2" 300 RF
Set Press. 1410 PSI **Back Press.:** 0 PSI **Cold/Diff Set Press:** **Temp:** **Cap:** 8995 SCFM
Lift Lever **Cap Assembly:** Closed **Code Symbol:** UV **CRN#:** 0G4369.5C

CUSTOMER INSTRUCTIONS

Instructions: Pretest, Service, and Test **Pretest Required?** **Reset Required?**
Replaces UVL ID#: **Replaces Valve Serial# :** **Replaces Valve Cust ID#**
RESET INFO: **New Pressure:** **New Cold/Diff Set:** **New Capacity:** **New Model:**

CONDITION AS RECEIVED

Visual Condition: Good **Data Plate Condition:** OK **Date of last service:** 2/04
Seal Condition: **Top:** Intact **Bottom:** N/A **Insignia:** TYCO **Fittings Attached:** **Inlet:** **Outlet:**
Inlet: Oily **Inlet Plugged:** **Outlet:** Oily **Outlet Plugged:** **Initial Insp. Signoff:** Grant Watson

PRETEST 1

Simmer: 1409 PSI **Set Press:** 1416 PSI **Reseat:** 1211 PSI **Leakage:** 0 BPM **Test Gauge:** FSJ 1+2
Tested By: Grant Watson **Pretest Comments:** SLIGHT LEAKAGE FROM PILOT VENT.

PRETEST 2

Simmer: PSI **Set Press:** PSI **Reseat:** PSI **Leakage:** BPM **Test Gauge:**
Tested By: **Pretest Comments:**

COMPONENTS INSPECTION

ITEM	CLEAN	OILY	RUSTY	CARBON	OTHER	COMMENTS	OK /		
							REPLACED	REPLACED?	REPAIRS PERFORMED
MAIN VALVE COMPONENTS INSPECTIO									
BODY	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
BONNET	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
PISTON	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
PISTON SLEEVE	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
SOFT GOODS KIT MAIN	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Worn	REPLACE	<input checked="" type="checkbox"/>	
TUBING	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
DISC	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
NOZZLE	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
SPRING and BUTTONS	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			<input type="checkbox"/>	
CONNECTION ENDS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
OTHER	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			<input type="checkbox"/>	
PILOT VALVE COMPONENTS INSPECTIO									
BODY	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
CAP	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
ADJUSTING SCREW	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
PILOT SPRING	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
DISC	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
NOZZLE	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
VENT	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
BLOWDOWN ASSY	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
PISTON	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
GUIDE	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
BONNET	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	
SOFT GOODS KIT PILOT	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Worn	REPLACE	<input checked="" type="checkbox"/>	
OTHER	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			<input type="checkbox"/>	
OTHER	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			<input type="checkbox"/>	
OTHER	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			<input type="checkbox"/>	

DISC: : **ACT -** N/A **NOZZLE:** MIN - **ACT -** N/A **NUMBER:**

Comments:



PRV INSPECTION AND TEST REPORT

BRANCH: Fort St John

UVL ID#: 2288F

Work Order: 307575

Customer PO#:

Disassembly: RYAN VINCENT

Inspection: RYAN VINCENT

Reassembly: RYAN VINCENT

FINAL TEST

Test Medium: Air

Simmer: 1408 PSI

Set Pressure: 1410 PSI

Reseat: 1325 PSI

Leakage: 0 BPM

B.P. Test: 60 PSI

Cold/Diff Set: PSI

ADJ. RING SETTING (NOTCHES): Upper: N/A

Lower: N/A

Test Gauge: FSJ 1+2

Set Press Def: POP

Tested by:

FINAL INSPECTION:

SEAL: Top: Bottom: End Protectors Installed: Painted: Palletized: Ship Container: Flex Gaskets Supplied:

Final Inspection: Grant Watson

Customer Inspection:

Comments: