

TREATER / FWKO

pics 3027-3132

New Used Sweet Sour

REV.2 01-07-15

1.0 DESCRIPTION			
Job#	B1356	Date	May 4/15
Diameter	30"	Type	Horizontal
Manufacturer	Legrand	Length S/S	17'
A#	209389	Date Built	1983
CRN#	E8055-2	Serial Number	83-25-01
Design Pressure	125psi	Corrosion Allowance	.125
Radiography	RT-3	Design Temperature	220 F
PWHT	N/A	Inlet Deflector	-
Internal Coating	NO	Insulation	NO
Phases	<input type="checkbox"/> 2Phase <input checked="" type="checkbox"/> 3Phase	Additional	
1.1 VESSEL CONNECTIONS			
Inlet	3" 150 RF	Drain	1" 150 RF
Outlet	2" 150 RF	Oil Level Control	2" NPT
H2O Level Control	2" NPT	Oil Level Gauge	(2) 3/4" NPT
H2O Level Gauge	(2) 3/4" NPT	Oil Out	2" 150 RF
H2O Out	1" NPT	PI	1/2" NPT
PSV	1 1/2" NPT	TI	3/4" NPT
TC/HTSD	(2) 3/4" NPT	HLSD	2" NPT
Anode	N/A	LLSD	2" NPT
Manway	30" 150 RF	Sample Point	
Inspection	N/A	Additional	14" X 24" Gas boot
2.0 FIRE TUBE			
Dimensions	8 1/2" X 10' 6"	Flame Arrestor	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
BTU Rating	500,000 BTU	Additional	needs burner upgrade

Drawings Available YES NO

Notes: 10" X 32" 50psi/200 F Fuel Gas Scrubber
 (1) Fisher 627 1" NPT - (5) Fairchild 1/4" NPT
 (2) Kimray 2" NPT dump valves - (2) Transparent sight glass
 Amot HPSD - 2" Northstar junior meter run

Building 8' X 17' 6" X 8' H s/f shed - needs to be repackaged
 Skid 8' X 18' X 8" Channel - checker floor - roll ends
 Shipping 8' 3" X 22' 6" X 9' - Floor is good - sitting in Red Deer Yard
 - needs to be repackaged.