



Job No.	2900	NTS	KM	L2900-1
SCALE	PROJ. ENGR	DATE	01.07.04	R. DUDDEK
DATE	01.07.04	CLIENT	ANADARKO CANADA CORP.	
DRAWING NO. L2900-1				
REV				
1				

TITLE: 3"-600# METER SKID w/ SCADA SOUR SERVICE PIPING PLAN & ELEVATIONS

MOSS FABRICATION LTD. CALGARY ALBERTA

REVISIONS

No	DESCRIPTION	DATE	DRN	APP'D	DATE
1	CHANGED TO TOL'S	01.07.12	GDS		
0	ISSUED FOR APPROVAL	01.07.04	RD		

10 UNITS REQ'D

- PAINT:
- SP-6 SANDBLAST
  - (1) S/C RUSTEX PRIMER
  - (1) S/C INDUSTRIAL ENAMEL (ONE COLOR)

- BUILDING:
- 6'-0" x 7'-0" x 7'-0" EAVE, 1:12 SHED ROOF
  - 22 GA GALVALUME STEEL EXTERIOR
  - 24 GA FLUTED ALUMINUM LINER
  - R-12 INSULATION
  - (1) 2'-8" x 6'-8" SINGLE MANDOR c/w IWG WINDOW, LOCKING PANIC HARDWARE, CHECK CHAIN
  - (1) 8" x 8" STAMPED ALUMINUM LOUVRES w/ SLIDING CLOSER
  - (1) 12,000 BTU CIS CAN HEATER c/w THERMOSTAT, START CABLE, SAFETY GRILL AND 12 VOLT EXP. PROOF HOOK-UP, VENT HOOD

- SKID:
- 6'-0" x 7'-0" x 5" @ 6.7# MAIN MEMBERS
  - (4) LIFT LUGS
  - 3/16" CHECKER PLATE FLOORING
  - 2" FOAM INSULATION

- PIPING:
- 3" PIPING, SCH-80 BUTTWELD A106B
  - 100% RADIOGRAPHY, STRESS RELIEVED
  - HYDROTEST
  - 1 1/2" AND SMALLER-3000# THREADED, SCH-80

- NOTES:
- TUBING / TUBE FITTINGS:
  - TUBING: 304 SS w/ SS SWAGELOCK TUBE FITTINGS