

Apex Valve Services

- ABSA (ASVS #64) CERT. - API SPEC. Q1(5th ED.)

Date: 26-Feb-13

PRV WT #SL **77098**

Customer Info	Company:	CNRL	Customer WO#:		Customer PO#:	U13621500-N239
	Contact:	CHRIS/AL	Customer AFE:		Invoiced:	<input type="checkbox"/> Invoice #: 0
	Phone:	(780) 891-3790	Area:	BRINTNELL		
	Fax:		Location:	12-9-81-22W4 INLET SEPARATOR 340		

Valve Info	ValveID:	A454725	Top Type:	C.C.	Temp:	60 F
	Serial#:	B131749X-1-2	Size:	3K4	Cold Set:	-
	Manufacturer:	CONSOLIDATED	Set Pres:	334 PSI	CRN#:	OG5530.52
	Model#:	1910KC	Capacity:	12819 SCFM	Connection Type:	FLANGE
	In Flange Size:	3" 300 RF	Back Pressure:	-	Internal Valve#:	-
	Out Flange Size:	4" 150 RF	Code Symbol:	UV/NB	Internal Basket#:	-

Receive Insp	Visual Condition:	FAIR	Data Plate Cond:	LEGIBLE
	Top Seal:	INTACT	Body:	FAIR
	Bottom Seal:	INTACT	Inlet:	SOME DEBRIS
	Insignia:	BE	Outlet:	RUSTY

Cust Instructions	Pretest Required:	<input type="checkbox"/>	Reset Required:	<input type="checkbox"/>	Customer Instructions:
	Pre Test By:	-	Set Pres Before Reset:		RECONDITION FROM STOCK
	Pre Test Sim:		Cap Before Reset:		
	Pre Test Set:		Set Pres After Reset:		
	Pre Test Gauge:		Cap After Reset:		
	Pre Test Leakage:		Cold Set After Reset:		Service Valve is in

Component Check List	As Found Condition	Parts Comment	Replace	Price
COMP SCREW & LOCK NUT	OK		No	\$0.00
BONNET/BODY/CAP	OK		No	\$0.00
STUDS & NUTS	OK		No	\$0.00
SPINDLE	WORN		Yes	\$886.15
SPRING	OK		No	\$0.00
DISC SEAT	PITTED (0.498)		Yes	\$546.15
NOZZLE SEAT	PITTED (0.556)	MACHINE/LAP/POLISH (1.5HR)	No	\$142.50
BEARING POINT	WORN		Yes	\$1,923.07
RING PIN (S)	OK		No	\$0.00
GUIDE	OK		No	\$0.00
GASKETS	FLATTENED		Yes	\$276.65
RF	OK		No	\$0.00
SHIP PARTS			No	\$25.00
VALVE REPAIR & LABOUR			No	\$270.00
FLANGE GASKETS			No	\$18.75

Final Test	NB18/OEM SetPres Def:	Seals Inst:	TOP & BOTTOM	
	POP	Final Cap:	12819 SCFM	
	Test Medium:	AIR	Back Pres Test:	30 PSI
	Test Gauge ID:	G19-G20	Paint:	RED
	Simmer:	327 PSI	Protectors:	FLANGE
	Final Set Pres:	334 PSI	Finished By:	LANCE KENDALL
	Blow Down:	- 7	Final Test By:	CAMERON COURTS
	Model # Change:	-	Shipped With:	AVS
	ServComp:	28-Feb-13	Ship Date:	02-Mar-13

Cost Summary	New Valves:	\$0.00
	Parts Total:	\$3,650.77
	Shop Supplies:	\$51.00
	Labour:	\$412.50
	Shipping:	\$25.00
	Other:	\$0.00
	SUB TOTAL:	\$4,139.27
	GST:	\$206.96
	TOTAL:	\$4,346.23
	Customer Signature:	

Leak Test Per Mfg Spec/API 527: 0 BPM @ 90%

Comments: TO BE INSTALLED IN PLACE OF S/N: 537874-2-A10