



Mountain West Services Ltd.

Inspection Report - CNRL2 # 10555

[\[www.mtnwest.ca\]](http://www.mtnwest.ca) [\[Company Index Page\]](#) [\[Vessels\]](#) [\[Pipelines\]](#) [\[SMART\]](#) [\[Incidents\]](#) [\[Work Orders\]](#) [\[Management of Change\]](#)

80683- #2 ELECTRIC DE-SALTER

VT External

Province:	Alberta	Manway:	Yes
District:	SPLT	Coating:	No
Location:	STURLS GAS PLANT	Inspect Date:	8/14/2012
LSD:	02-02-069-22W5	Inspection Interval:	60
CRN:	B8744.2	Next Inspection:	8/14/2017
Skid/Equipment Number:	V20-137	MAWP:	300 PSI 2068.44 KPa
Service:	Sour	Temperature:	250 F 121.11 C
Status:	Out Of Service	Outstanding NCRs:	0

General:			
Safety Valves:			
PSV <u>NON-CODE</u> Protects the Shell Of the Vessel. Set Pressure of 5 PSI / 34 KPa. Capacity: SCFM / m3/min			
Status: Out Of Service	Examination Methods: VT	Access: External	Cleaning:
External:			
All visible shell surfaces and nozzles appear in good condition. Name plate is intact and legible. Vessel supports, foundation, and external coating appear good. Confirm electrical bonding and equipment grounding. Associated piping supports and components appear in good condition and alignment with no signs of leaks or defects present at the time of inspection. Verify PSV protection and PSV's are properly installed with any block valves locked/sealed open. Verify vessel has Alberta CRN and A# stamping or Unique Identifier, PSV has correct set pressure and MWS tagging, and was last serviced within the required interval guidelines. Assign inspection interval.			
Internal:			

Recommendations:

The vessel is currently out of service and requires a thorough inspection prior to going back into service.

Repair any damaged cladding to prevent external rusting and corrosion.

Inspector's Declaration: I have witnessed the above inspections and certify that they have been done in accordance with our manual and that the information is accurate. I certify that the status of the pressure equipment detailed here is:

Suitable to be returned to service: Yes

Repairs complete: N/A

Repairs are still required: No

Suggested Inspection Interval: 60

Inspector: Jay Bourne, MWS **Date:** 8/14/2012

Chief Inspector: I certify that the information on this report is true and that all inspections required by the Owner/User Quality Assurance Program# AQP-9013 which expires in 12/11/2013 have been done.

Chief Inspector: Jim Damiani Cert 00037

Date: 1/28/2013

[\[Back To Start Page\]](#) [\[MtnWest.Ca\]](#)