



NOT BE RE-PRODUCED OR DISTRIBUTED  
 WITHOUT THE PRIOR WRITTEN CONSENT OF  
 ENERGY INDUSTRIES INC.

**GENERAL SPECIFICATIONS**

OVERALL PACKAGE LENGTH (FT)	49'-4 3/4"
OVERALL PACKAGE WIDTH (FT)	24'-3"
OVERALL PACKAGE HEIGHT (FT) (LESS STACK)	20'-4 3/4"
OVERALL PACKAGE WEIGHT (LBS)	466
GLYCOL STORAGE CAPACITY (U.S. GAL.)	466
WASTE OIL STORAGE CAPACITY (U.S. GAL.)	103
SOUL WASTE OIL STORAGE CAPACITY (U.S. GAL.)	56 U.S. GAL.
CRANE RAILS	125 U.S. GAL.
BRIDGE CRANE	YES <input type="checkbox"/> NO <input type="checkbox"/>
SEAL PAN	YES <input type="checkbox"/> NO <input type="checkbox"/>
LOADING METHOD	SWIFT <input type="checkbox"/> ROLL <input type="checkbox"/> CRANE <input type="checkbox"/>
PROCESS GAS	SWEET <input type="checkbox"/> SOUR <input type="checkbox"/> ACID GAS <input type="checkbox"/> H <sub>2</sub> S <input type="checkbox"/>

NOTES:  
 1. ALL DIMENSIONS TAKEN FROM BOTTOM OF SHIP.  
 2. ALL OTHER NOTES FOUND ON DWG. #FLOW.  
 3. ALL SKID EDGE CONNECTIONS CONSTRUCTED TO ±1/8" TOLERANCE.

**CUSTOMER CONNECTIONS**

- 1 INITIAL SUCTION
- 2 FINAL DISCHARGE
- 3 HIGH PRESSURE VENT HEADER
- 4 SCRUBBER DRAIN HEADER
- 5 FUEL GAS INLET
- 6 CYLINDER LUBE OIL FILL
- 7 LOCAL CYLINDER LUBE OIL FILL
- 8 LOCAL ENGINE/COMPRESSOR LUBE OIL FILL/DRAIN
- 9 ENGINE/COMPRESSOR LUBE OIL FILL
- 10 WASTE OIL DRAIN
- 11 WASTE OIL PUMP OUT
- 12 START GAS INLET
- 13 STARTER VENT
- 14 LOW PRESSURE GAS VENT
- 15 LOCAL COMPRESSOR OIL FILL
- 16 LOW PRESSURE PUMP VENT
- 17 INSTRUMENT AIR VENT
- 18 INSTRUMENT AIR HEADER
- 19 GLYCOL FILL
- 20 GLYCOL DRAIN
- 21 HEATER GLYCOL SUPPLY
- 22 WASTE OIL DRAIN
- 23 SOUR WASTE OIL DRAIN
- 24 SEAL POT OIL FILL
- 25 3"-PIPE (C/W BIRSCREEN) VENTED ABOVE BLOC. EAVE
- 26 1"-PIPE (C/W BIRSCREEN) VENTED ABOVE BLOC. EAVE
- 27 2"-3000# (NPT)
- 28 1"-PIPE (C/W BIRSCREEN) VENTED ABOVE BLOC. EAVE
- 29 1"-PIPE (C/W BIRSCREEN) VENTED ABOVE BLOC. EAVE
- 30 3/4"-RUBBER HOSE
- 31 2"-150# RFSW
- 32 2"-150# RFSW
- 33 1"-PIPE (C/W BIRSCREEN) VENTED ABOVE BLOC. EAVE
- 34 2"-3000# (NPT)

No.	REVISION	DATE	BY
2	AS BUILT	03/03/04	CD
1	ISSUED FOR CONSTRUCTION	12/11/03	CD
0	ISSUED FOR APPROVAL	11/26/03	CD

  

TITLE	GENERAL ARRANGEMENT	CUSTOMER	ENERGY INDUSTRIES INC.
NO.	4303 - 11TH STREET N.E. CALGARY ALBERTA CANADA	DESIGN COMPANY	WALKESHA E3324GSI / AREL JOK/7-2
SCALE	1/2"=1'-0"	DATE	11/26/03
DRWING NO.	1105-CA	DATE RELEASED	03/04/04
REV.	2/	REV. BY	MLL