



PRV INSPECTION AND TEST REPORT

BRANCH: Fort St John

UVL ID#: 8946F

Work Order: 307836

Customer PO#:

Customer: CANADIAN NATURAL RESOURCES LIMITED
Facility: KOBES
A#: A491800
Cust. Ref.: FSJ 4899
Cust. WO#:

LSD: a-017-J/94-B-09
Vessel SN: N/A
Valve PO:
Cust AFE#:

Date: 11/22/2011
PSV Location: DEHY BLDG CONTACTOR
Cust Id: PSV2000
PO LINE#:
Cost Centre#:

VALVE DATA

Man.: FARRIS Model: 27FA45-M20 Serial: 451002-2-KE Seat: POP
Conn. Flanged Inlet: 1.5" MNPT Orifice: F Outlet: 2" FNPT
Set Press. 1410 PSI Back Press.: 0 PSI Cold/Diff Set Press: Temp: Cap: 8819 SCFM
Lift Lever Cap Assembly: Closed Code Symbol: UV CRN#: 0G0386.9C

CUSTOMER INSTRUCTIONS

Instructions: Pretest, Service, and Test Pretest Required? [checked] Reset Required? []
Replaces UVL ID#: Replaces Valve Serial#: Replaces Valve Cust ID#
RESET INFO: New Pressure: New Cold/Diff Set: New Capacity: New Model:

CONDITION AS RECEIVED

Visual Condition: Good Data Plate Condition: OK Date of last service: 6/08
Seal Condition: Top: Intact Bottom: N/A Insignia: UVL Fittings Attached: Inlet: [] Outlet: []
Inlet: Carbon Inlet Plugged: [] Outlet: Carbon Outlet Plugged: [] Initial Insp. Signoff: Tara Stones

PRETEST 1

Simmer: 1400 PSI Set Press: 1436 PSI Reseat: 1301 PSI Leakage: AUDIBLE BPM Test Gauge: FSJ 1+2
Tested By: Grant Watson Pretest Comments:

PRETEST 2

Simmer: PSI Set Press: PSI Reseat: PSI Leakage: BPM Test Gauge:
Tested By: Pretest Comments:

COMPONENTS INSPECTION

Table with columns: ITEM, CLEAN, OILY, RUSTY, CARBON, OTHER, COMMENTS, OK / REPLACED, REPLACED?, REPAIRS PERFORMED. Rows include DISC, NOZZLE, CAP-LEVER ASSY, COMP SCREW and LOCKNUT, SPRING and BUTTONS, SPINDLE / STEM, STEM RETAINER, DISC HOLDER, GUIDE / UPPER RING, LOWER RING, RING PIN(S), BELLOWS, GASKET / SEALS, CONNECTION ENDS, OTHER.

DISC: Min: .734 ACT - .748 NOZZLE: MIN - .950 ACT - .955 NUMBER: N/A

Comments: NOZZLE CLOSE TO SPEC, POSSIBLE REPLACEMENT NEXT SERVICE.

Disassembly: Harley Anderson Inspection: Harley Anderson Reassembly: Harley Anderson

FINAL TEST

Test Medium: Air Simmer: 1408 PSI Set Pressure: 1410 PSI
Reseat: 1313 PSI Leakage: 15 BPM B.P. Test: 60 PSI Cold/Diff Set: PSI
ADJ. RING SETTING (NOTCHES): Upper: N/A Lower: N/A Test Gauge: FSJ 1+2 Set Press Def: POP
Tested by:

FINAL INSPECTION:

SEAL: Top: [checked] Bottom: [] End Protectors Installed: [checked] Painted: [checked] Palletized: [checked] Ship Container: [] Flex Gaskets Supplied: [checked]
Final Inspection: Tara Stones Customer Inspection:
Comments: