

LH-14395 1.2 MMBTU/Hr. Lineheater

Plains 54" OD x 20' Heater Shell Insulated & Metal Clad for 12' with 8' Inside Building

14" OD U-shaped Firetube with Flame Arrested 1,111,500 BTU/Hr. Burner/Pilot System

30" OD x 56" Glycol Expansion Pot with HLSD, Siteglass, Wenco Thief Hatch & Access Ladder

6 Pass Preheat Coil: 3" 1500 ANSI RTJ 3054 PSI, 1/16" Corrosion Allowance, PWHT & 100% Radiography

8 Pass Reheat Coil: 3" 900 ANSI RTJ 1813 PSI, 1/16" Corrosion Allowance, PWHT & 100% Radiography

A#438680, CRN N9595.213, SN 2054CBA

Plains 10" x 36" 150# Fuel Gas Scrubber

12'6" x 16' x 12'6" High Gable Style Self Framing Building w/(2) Doors w/windows, (2) Windows, Vent & removable panel

12'6" x 30' Structural Steel Skid