



Client:
CNRL

PRESSURE EQUIPMENT DATA REPORT

EQUIPMENT GENERAL INFORMATION

District:	Fort St John		
Facility:	JULY LAKE		
Location /LSD:	A-071-G/094-P-10	Operating Province:	British Columbia
Equipment Name:	GLYCOL CONTACTOR		
Equipment Status:	Not In Service	Orientation:	Vertical
Skid No.:	Unit:		

EQUIPMENT STATIC DATA

AB Registration No.:	2877363	Serial No.:	93C-4948-01	
Registration No./Other:	PV104830	Equipment No.:		
CRN NO.:	H-3319-1	Unique ID No.:		
National Board No.:	N/A	Oncor ID No.:	173945	
Manufacturer:	Alco	Year Built:	1993	
MAWP:	1415.00 (psi)	9756.14 (Kpa)	Temperature:	150.00 (F) 65.56 (C)
Diameter.:	36.000 (In)	914.400 (mm)	Length:	(In) 0.00 (mm)
Radiography:	RT1		Heat Treatment:	Yes
Corrosion allowance:	0.125 (In)	3.175 (mm)	MDMT:	-20.00
Lining Or Coated:			Painted:	Yes
Insulated:	No		Internally Clad:	No
Hand Hole:	No		Support Type:	Skirt
Manway:	No		Manway Size(In):	
Capacity/Volume(m3):			Nozzle Rating:	

MATERIALS/COMPONENTS

Name	Joint Efficiency	Outside Diameter(in.)	Head Type	Material Type	Stress Value (PSI)	Nominal Thickness(In.)
SHELL	1.00	36.000		SA-516 70	17500	1.75
HEAD	1.00	36.000	Ellipsoidal	SA-516 70	17500	1.66

PIPING STATIC DATA

Primary Flange Rating:	600	ASME B16.5 - Table 2-1.1 @ 150F:	1480 (psi)	
Pressure Use For TMin:	Vess Design Press	Piping Operating Press:	1415 (psi)	
Stress Value:	20000 (psi)	E Value:	1.00	Joint: SMLS

SERVICE CONDITIONS

Sweet	Sour	Oil	Gas	Water
Amine	LPG	Condensate	Air	Glycol

COMMENTS

--



LSD



NAMEPLATE



OVERALL