



SHOP NOTE: NO GAP ALLOWANCE IS INCLUDED IN CUT LENGTHS

BILL OF MATERIAL		
ITEM	QTY	DESCRIPTION
1	2	W10 @ 22 x 28'-0" LG
2	2	W10 @ 22 x 90" LG
3	2	W6 @ 15 x 76 7/8" LG
4	2	W6 @ 15 x 90" LG
5	2	C6 @ 8.2 x 90" LG
6	3	3" x 3" x 1/4" ANGLE x 39 5/8" LG
7	2	3" x 3" x 1/4" ANGLE x 36 1/2" LG
8	3	3" x 3" x 1/4" ANGLE x 37 3/8" LG
9	1	3" x 3" x 1/4" ANGLE x 29 15/16" LG
10	1	3" x 3" x 1/4" ANGLE x 28 9/16" LG
11	2	4" SCH 40 SML'S PIPE x 102" LG
12	4	1/4" PL x 4 1/4" x 6" LG
13	1	3/16" CHECKER PL 96" x 120" LG
TOTAL SKID WT. 3150 Lbs		

NO.	DATE	REVISIONS	DRAWN	CHECK	DESIGN	APPR.
A	99.11.17	ISSUED FOR APPROVAL	SPB			
			DRAFTING	ENGINEERING		

PRIORITY PROJECTS LTD.

1603-8 STREET, NISQU, ALBERTA T9E 5T5
 TELEPHONE: (780) 955-3320 FAX: (780) 955-2561

WELLHEAD LINEHEATER
SKID DETAILS

CUSTOMER NAME	SCALE	DRAWING NUMBER	REV.
KAISER ENERGY LTD.	NTS	5295-400	A
LSD NO.	7-35-83-19W 6M		