



Mountain West Services Ltd.

Inspection Report - Barrick # 8949

[\[www.mtnwest.ca\]](http://www.mtnwest.ca) [\[Company Index Page\]](#) [\[Vessels\]](#) [\[Pipelines\]](#) [\[SMART\]](#) [\[Incidents\]](#) [\[Work Orders\]](#) [\[Management of Change\]](#)

2638748- SEPARATOR

VTI External

Province:	Alberta	Manway:	NO
District:	NORTHERN - AB	Coating:	No
Location:	PUSKWA	Inspect Date:	12/17/2008
LSD:	08-05-072-26W5	Inspection Interval:	60
CRN:	K0965.2	Next Inspection:	12/17/2013
Skid/Equipment Number:	PKG50493	MAWP:	250 PSI 1723.7 KPa
Service:	Sweet	Temperature:	100 F 37.78 C
Status:	Spare	Outstanding NCRs:	0

General:

Installation inspection of vessel. No deficiencies found at time of inspection. Installation inspection includes checking vessel and associated piping are secure and properly supported. Verify no physical damage has occurred during transportation.

Safety Valves:

PSV [MWS66484](#) Protects the Shell Of the Vessel. Set Pressure of 250 PSI / 1723.7 KPa. Capacity: 1856SCFM / 52.56m3/min

Status: Spare	Examination Methods: VTI	Access: External	Cleaning: Good
----------------------	---------------------------------	-------------------------	-----------------------

External:

All visible shell surfaces and nozzles appear in good condition. Name plate is intact and legible. Vessel supports, foundation, electrical grounding to skid and external coating appear good. Associated piping, supports and components appear in good condition and alignment. Verify PSV protection and PSV's are properly installed with any block valves locked/sealed open. Verify vessel has Alberta CRN and MWS tagging, PSV has correct code stamp, set pressure and MWS tagging, and was last serviced within the required interval guidelines. Assign inspection interval.

Internal:

Recommendations:

Inspector's Declaration: I have witnessed the above inspections and certify that they have been done in accordance with our manual and that the information is accurate. I certify that the status of the pressure equipment detailed here is:

Suitable to be returned to service: Yes

Repairs complete: N/A

Repairs are still required: No

Suggested Inspection Interval: 60

Inspector: Duane Paetkau Cert #000087 **Date:** 12/19/2008

Chief Inspector: I certify that the information on this report is true and that all inspections required by the Owner/User Quality Assurance Program# AQP-9013 which expires in 12/11/2010 have been done.

Chief Inspector: Jim Damiani Cert 00037
Date: 11/28/2010

[\[Back To Start Page\]](#) [\[MtnWest.Ca\]](#)