

	10800 - API	10600- Heavy Duty Oil & Gas	10700-Extreme Duty, Oil & Gas
Product			
Self Distributing over liquid surface	Yes	Yes	Yes
Density	.5 kg/l	0.46 kg/l +/- 2%	0.375 kg/l +/- 2%
Weight per tile	325g	285g	260g
Dimensions per tile	63mm height, Diagonal measure 215mm, parallel side 188mm	63mm height, Diagonal measure 215mm, parallel side 188mm	63mm height, Diagonal measure 215mm, parallel side 188mm
Operating Temperature	Outside Ambient to 50° C Continuous Duty	Outside Ambient to 90° C Continuous Duty	Outside Ambient to 100° C Continuous Duty
Static Dissipative	No	Yes	Yes
Coverage	34 tiles per m ²	34 tiles per m ²	34 tiles per m ²
Material	100% Recycled Polypropylene	Dupont Zytel 101 6/6	Dupont Zytel 153 6/12
Life Expectancy	25 years	Application dependant	Application dependant
Packaging	Bulk Bag (Type D FIBC)	Bulk Bag (Type D FIBC)	Bulk Bag (Type D FIBC)
Typical Applications	Tank, ponds and lagoons. Fire water, fresh water, waste water, manure	Oil, Heavy crude, diesel, gasoline	SAGD, Dilbit, low density hydrocarbons
Benefits	Organic growth and bird deterrent, minimizes evaporation, odour and emissions reductions	Minimizes evaporation and heat loss, odour and emissions reductions,	Minimizes evaporation and heat loss, odour and emissions reductions,