



208284

Field Inspection Report

Vessel # 208284

Client	Canadian Natural Resources Ltd.		Inspection Date	2003/02/14	
Prov. Reg.#	208284		Insp. Type	VE/UT	
Equipment	Glycol Contactor		Location	Endiang	
Tag/Equip. #			LSD	13-3-35-16W4	
Vessel Status	In Service		Comp./Unit		
Manufacturer	Propak	Serial #	83191A	MAWP/Temp	1319 psi 100 F
CRN #	E8482.2	Shell Material		Shell Thick.	0.844 in
Corrosion All.	in	Head Material		Head Thick.	0.750 in
Manway	No	Head Material 2		Head Thick. 2	in
Coating	No	Channel Material		Channel Thick.	in
Diameter	16 in	Length	in	Height	360 in
Year Built	1983	Next Inspection	2007		Next Insp. Type
Service	Sweet			RT	2
				HT	Yes
				Job #	03-097

PSV #.	CF-19199KA				
Mfg.	Farris	Serial #	CF19199KA	Set Pressure	1310 psi
Type/Model	2741	Capacity	2647 SCFM	Size	0.750 in
Date of Service	2001/05/14	Next Service	2005	Service Co.	King Valve

Observations:

External
 Building is well maintained. Vessel is supported by a 16" skirt that is bolted to the floor. PSV is located on the shell. PSV vents to atmosphere. Piping is in fair condition and well supported. Some minor surface corrosion is present. Gauges are in good condition. Data plate information is clear and correct. Bolting and connections appear in good condition. Paint and external are in good condition. No ground.

Internal
 None at this time

AB-40 to be attached

Field Inspection Report

Vessel # 208284

UT

Measurements in inches
Shell - 0.749 to 0.764
Bottom Head - 0.824 to 0.869
Top Head - Not accessible

Recommendations:

No recommendations at this time.

Inspector: Sean Zitaruk

Reviewed by:



AB-40 to be attached