



208008

Field Inspection Report

Vessel # 208008

Client	Canadian Natural Resources Ltd.		Inspection Date	2003/02/17	
Prov. Reg.#	208008		Insp. Type	VE/UT	
Equipment	Separator		Location	Endiang	
Tag/Equip. #			LSD	6-28-34-15W4	
Vessel Status	In Service		Comp./Unit		
Manufacturer	Flo-Skid	Serial #	1011	MAWP/Temp	600 psi 60 F
CRN #	E6479.2	Shell Material		Shell Thick.	0.500 in
Corrosion All.	in	Head Material		Head Thick.	0.500 in
Manway	No	Head Material 2		Head Thick. 2	in
Coating	No	Channel Material		Channel Thick.	in
Diameter	20 in	Length	in	Height	120 in
Year Built	1982	Next Inspection	2007	RT	2
Service	Sweet			Next Insp. Type	NA
				Job #	03-097
PSV #.	83C0011				
Mfg.	Consolidated	Serial #	83C0011	Set Pressure	230 psi
Type/Model	1970C2	Capacity	943 SCFM	Size	1,000 in
Date of Service	2001/05/17	Next Service	2005	Service Co.	King Valve

Observations:

External
 Building is well maintained. Vessel is supported by a 20" skirt that is bolted to the floor. PSV is located on the outlet piping. PSV vents to atmosphere. Piping is well supported and in good condition. Gauges are in good condition. Data plate information is clear and correct. Bolting and connections appear secure. Paint and external are in good condition. No ground.

Internal
 None at this time

AB-40 to be attached

RAE Inspection Service (1979) Ltd.
#111,4808 ; 87 Street, Edmonton, Alberta T6E 5W3
Phone: (780) 469-2401 Fax (780) 468-2422

Field Inspection Report

Vessel # 208008

UT

Measurements in inches
Top Head - Not accessible
Shell - 0.652 to 0.668
Bottom Head - 0.517 to 0.548

Recommendations:

No recommendations at this time.

Inspector: Sean Zitaruk

Reviewed by:



AB-40 to be attached