



**V-200**  
 GLYCOL CONTACTOR  
 SIZE: 610 mm Ø x 7925 mm S/S  
 MAMP: 5706 kPa @ 65°C  
 CA: 3.2 mm  
 CRN: L-9722.21  
 A No.: 498800  
 MFG: OPSCO

**V-230**  
 FLASH TANK  
 SIZE: 323 mm Ø x 1524 mm S/S  
 MAMP: 1862 kPa @ 65°C  
 CA: 3.2 mm  
 CRN: L-5291.21  
 MFG: OPSCO

**V-250**  
 FUEL GAS SCRUBBER  
 SIZE: 219 mm Ø x 711 mm S/S  
 MAMP: 1724 kPa @ 65°C  
 CA: 1.6 mm  
 CRN: K-1773.312  
 MFG: OPSCO

**BH-295**  
 BUILDING HEATER  
 MFG: CATADYNE  
 MCL: WX 24224  
 DUTY: 22.60 BTU/HR

**P-215 & 216**  
 GLYCOL CIRCULATION PUMPS  
 MFG: KIMRAY  
 MCL: 9016 PV  
 CAP: 30 GPH

**E-240**  
 AIR/GLYCOL EXCHANGER  
 SIZE: 42 mm Ø x 3048 mm LONG

**E-210**  
 GAS/GLYCOL EXCHANGER  
 SIZE: 114 mm Ø x 1524 mm LONG

**E-241**  
 HP GLYCOL FILTER  
 MFG: NOMATA  
 MCL: IS21MANTHANT  
 MAMP: 822.9 kPa

**E-206**  
 CHARCOAL FILTER  
 MFG: CUNO  
 MCL: CT-102

**H-220**  
 GLYCOL RECONCENTRATOR  
 SIZE: 610 mm Ø x 2134 mm (REROLLER)  
 SIZE: 610 mm Ø x 1676 mm (SURGE)  
 DUTY: 250000 BTU/HR

REV.	DESCRIPTION	DATE	CHK	APP.	CLIENT
2	CHANGE TO ONEL TITELBLOCK	07-02-15	---	---	---
1	AS-BUILT, REPAIR FROM GLE. ORIGINALS	04-04-28	IRM	---	---
0	ISSUED FOR CONSTRUCTION - GLE. ENG.	03-11-20	ISM	---	---

  

REV.	DRAWING NO.	SCALE	JOB NO.	TITLE	DATE	DATE	DATE	DATE	DATE
2	KBB-171-220-0004	NTS	---	MECHANICAL FLOW DIAGRAM COMPRESSOR STATION DEHYDRATION	07-02-15	---	---	---	---
1	---	---	---	---	---	---	---	---	---
0	---	---	---	---	---	---	---	---	---

  

REV.	DRAWING NO.	SCALE	JOB NO.	TITLE	DATE	DATE	DATE	DATE	DATE
2	KBB-171-220-0004	NTS	---	MECHANICAL FLOW DIAGRAM COMPRESSOR STATION DEHYDRATION	07-02-15	---	---	---	---
1	---	---	---	---	---	---	---	---	---
0	---	---	---	---	---	---	---	---	---

