



PRV INSPECTION AND TEST REPORT

BRANCH: Grande Prairie

UVL ID#: 17801G

Work Order: 523928

Customer PO#:

Customer: CANADIAN NATURAL RESOURCES LIMITED
 Facility: POUCE COUPE SOUR
 A#: A463670
 Cust. Ref.:
 Cust. WO#:

LSD: 06-25-079-12W6M
 Vessel SN:
 Valve PO:
 Cust AFE#:

Date: 05/06/2013
 PSV Location: SEPARATOR
 Cust Id:
 PO LINE#:
 Cost Centre#:

VALVE DATA

Man.: MERCER Model: 81-17151T17G21S Serial: 133140 Seat: POP
 Conn. Threaded Inlet: 1" MNPT Orifice: E Outlet: 1" FNPT
 Set Press. 1440 PSI Back Press.: PSI Cold/Diff Set Press: Temp: Cap: 4956 SCFM
 Lift Lever Cap Assembly: Closed Code Symbol: UV CRN#: 0G8841.5C

CUSTOMER INSTRUCTIONS

Instructions: Pretest, Service, and Test Pretest Required? Reset Required?
 Replaces UVL ID#: Replaces Valve Serial#: Replaces Valve Cust ID#
 RESET INFO: New Pressure: New Cold/Diff Set: New Capacity: New Model:

CONDITION AS RECEIVED

Visual Condition: Fair Data Plate Condition: OK Date of last service: 06/10
 Seal Condition: Top: Intact Bottom: N/A Insignia: KGP Fittings Attached: Inlet: Outlet:
 Inlet: Oily Inlet Plugged: Outlet: Oily Outlet Plugged: Initial Insp. Signoff: Rico Santos

PRETEST 1

Simmer: 1436 PSI Set Press: 1437 PSI Reseat: 1271 PSI Leakage: 10+ BPM Test Gauge: 10K-1/5
 Tested By: Matt Leslie Pretest Comments:

PRETEST 2

Simmer: PSI Set Press: PSI Reseat: PSI Leakage: BPM Test Gauge:
 Tested By: Pretest Comments:

COMPONENTS INSPECTION

ITEM	CLEAN	OILY	RUSTY	CARBON	OTHER	COMMENTS	OK / REPLACED?		
							OK / REPLACED	REPLACED?	REPAIRS PERFORMED
DISC	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	Clean
NOZZLE	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	Clean
CAP-LEVER ASSY	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	Clean
COMP SCREW and LOCKNUT	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	Clean
SPRING and BUTTONS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	Clean
SPINDLE / STEM	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	N/A		<input type="checkbox"/>	
STEM RETAINER	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	N/A		<input type="checkbox"/>	
DISC HOLDER	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	N/A		<input type="checkbox"/>	
GUIDE / UPPER RING	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	Clean
LOWER RING	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	N/A		<input type="checkbox"/>	
RING PIN(S)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	N/A		<input type="checkbox"/>	
BELLOWS	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	N/A		<input type="checkbox"/>	
GASKET / SEALS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Worn	REPLACE	<input checked="" type="checkbox"/>	Replaced
CONNECTION ENDS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>		OK	<input type="checkbox"/>	Clean
OTHER	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>			<input type="checkbox"/>	

DISC: : SUB ACT - N/A NOZZLE: MIN - SOFT ACT - N/A NUMBER: 05-017

Comments:

Disassembly: Derrick Walpole Inspection: Derrick Walpole Reassembly: Derrick Walpole

FINAL TEST

Test Medium: Air Simmer: 1438 PSI Set Pressure: 1440 PSI
 Reseat: 1264 PSI Leakage: 0 BPM B.P. Test: 60 PSI Cold/Diff Set: PSI
 ADJ. RING SETTING (NOTCHES): Upper: N/A Lower: N/A Test Gauge: 10K-1/5 Set Press Def: POP
 Tested by:

FINAL INSPECTION:

SEAL: Top: Bottom: End Protectors Installed: Painted: Palletized: Ship Container: Flex Gaskets Supplied:

Final Inspection: Derrick Walpole Customer Inspection:

Comments: