



Mountain West Services Ltd.

Inspection Report - Barrick # 8287

[\[www.mtnwest.ca\]](http://www.mtnwest.ca) [\[Company Index Page\]](#) [\[Vessels\]](#) [\[Pipelines\]](#) [\[SMART\]](#) [\[Incidents\]](#) [\[Work Orders\]](#) [\[Management of Change\]](#)

2531786- FLARE KNOCKOUT

VT External

Province:	Alberta	Manway:	YES
District:	STURGEON LAKE	Coating:	No
Location:	STURLS	Inspect Date:	2/12/2010
LSD:	06-11-069-21W5	Inspection Interval:	60
CRN:	K2234.2	Next Inspection:	2/12/2015
Skid/Equipment Number:	PKG55552	MAWP:	75 PSI 517.11 KPa
Service:	Sour	Temperature:	200 F 93.33 C
Status:	Out Of Service	Outstanding NCRs:	0

General:

Safety Valves:

PSV [FLD2097](#) Protects the Shell Of the Vessel. Set Pressure of 15 PSI / 103.422 KPa. Capacity: 212SCFM / 6m3/min

Status: Out Of Service	Examination Methods: VT	Access: External	Cleaning: Good
-------------------------------	--------------------------------	-------------------------	-----------------------

External:

Non Code service - open to atmosphere. Out of service. All visible shell surfaces and nozzles appear in good condition. Name plate is intact and legible. Vessel supports, foundation, electrical grounding and external coating appear good. Associated piping, supports and components appear in good condition and alignment. No evidence of short studding or nut rounding at time of inspection. Verify vessel has Alberta CRN, A# stamping, Verify PSV protection and PSV's are properly installed with any block valves locked/sealed open. PSV has correct code stamp, set pressure and MWS tagging, and was last serviced within the required interval guidelines. Assign inspection interval.

Internal:

Recommendations:

The vessel is currently out of service and requires a thorough inspection prior to going back into service.

Inspector's Declaration: I have witnessed the above inspections and certify that they have been done in accordance with our manual and that the information is accurate. I certify that the status of the pressure equipment detailed here is:

Suitable to be returned to service: Yes	Repairs complete: N/A
Repairs are still required: No	Suggested Inspection Interval: 60
Inspector: Leo Nedelec, MWS Date: 2/16/2010	
Chief Inspector: I certify that the information on this report is true and that all inspections required by the Owner/User Quality Assurance Program# AQP-9013 which expires in 12/11/2010 have been done.	
Chief Inspector: Jim Damiani Cert 00037 Date: 2/27/2010	

[\[Back To Start Page\]](#) [\[MtnWest.Ca\]](#)