



ountain West Services Ltd.

## Inspection Report - CNRL # 7106

[\[www.mtnwest.ca\]](http://www.mtnwest.ca) [\[Company Index Page\]](#) [\[Vessels\]](#) [\[Pipelines\]](#) [\[SMART\]](#) [\[Incidents\]](#) [\[Work Orders\]](#) [\[Management of Change\]](#)

### 3138696- LINE HEATER

#### UT External

<b>Province:</b>	Alberta	<b>Manway:</b>	NO
<b>District:</b>	GPOU	<b>Coating:</b>	No
<b>Location:</b>	MONTNEY	<b>Inspect Date:</b>	10/23/2006
<b>LSD:</b>	09-33-074-11W6	<b>Inspection Interval:</b>	48
<b>CRN:</b>	N092.2P	<b>Next Inspection:</b>	10/23/2010
<b>Skid/Equipment Number:</b>	SKID022	<b>MAWP:</b>	10 PSI 68.948 KPa
<b>Service:</b>	Sour	<b>Temperature:</b>	249.8 F 121 C
<b>Status:</b>	In Service	<b>Outstanding NCRs:</b>	0

#### General:

2006 Ultrasonic Corrosion Survey.

#### Safety Valves:

<b>Status:</b> In Service	<b>Examination Methods:</b> UT	<b>Access:</b> External	<b>Cleaning:</b> Good
---------------------------	--------------------------------	-------------------------	-----------------------

#### External:

Refer to 2006 VT External inspection report as part of this thorough inspection.

#### Internal:

The line heater tube bundle nozzles were UT inspected for wall loss.

Hunt Inspections's Ultrasonic Corrosion Survey Project #C10093, as reported on Drawing #103, noted all nozzle thickness readings to be above ASME B31.3 code requirements at time of inspection. The calculated retirement date is 2026 with a program maximum of 20 years.

The associated piping was also inspected with no notable wall loss recorded.

Caution was generated onTML's 103-10 and 103-45. Calculations indicate the areas are well above minimum required thickness for design conditions.

The elbows appear to be at the low end of the 12.5% allowable mill undertolerance.

Next inspection is 4 years or 1/2 remaining life, whichever is less.

**Recommendations:**

Recommend 4 year interval for next UT inspection.

Ultrasonic Corrosion Survey due again in 2010.

**Inspector's Declaration:** I have witnessed the above inspections and certify that they have been done in accordance with our manual and that the information is accurate. I certify that the status of the pressure equipment detailed here is:

<b>Suitable to be returned to service:</b> Yes	<b>Repairs complete:</b> N/A
<b>Repairs are still required:</b> No	<b>Suggested Inspection Interval:</b> 48
<b>Inspector:</b> Duane Paetkau Cert #000087 <b>Date:</b> 3/12/2007	
<b>Chief Inspector:</b> I certify that the information on this report is true and that all inspections required by the Owner/User Quality Assurance Program# AQP-8047 which expires in 12/06/05 have been done.	
<b>Chief Inspector:</b> Jim Damiani Cert 00037 <b>Date:</b> 3/28/2007	

[\[Back To Start Page\]](#) [\[MtnWest.Ca\]](#)