



T-671 CONTACTOR
 SIZE: 864mm O.D. x 9957mm HIGH
 DESIGN PRESS.: 14500 kPa @ 65/-29°C
 3.18mm CORR. ALLOW.
 STRUCTURED PACKING

E-671 EXCHANGER
 TEMA TYPE NEN
 DESIGN PRESS.: 14500 kPa @ 93/-29°C

V-672 FLASH TANK
 SIZE: 610mm O.D. x 1676mm HIGH
 DESIGN PRESS.: 1034 kPa @ 93°C

P-673A/B GLYCOL PUMP
 MODEL: UNION TX-10
 6.67 USGPM 10 HP 460/3/60

V-674 FUEL GAS SCRUBBER
 SIZE: 273mm O.D. x 762mm S/S
 DESIGN PRESS.: 1034 kPa @ 65/-29°C
 3.2mm CORR. ALLOW.

F-675 FILTER
 SIZE: 219mm O.D. x 1219mm S/S
 DESIGN PRESS.: 1034 kPa @ 65°C
 3.2mm CORR. ALLOW.

F-676 FILTER
 SIZE: 356mm O.D. x 1067mm S/S
 DESIGN PRESS.: 1034 kPa @ 93°C
 3.2mm CORR. ALLOW.
 MODEL: DANVIC #FA1402

H-677 REGENERATOR
 REBOILER: 914mm O.D. x 3353mm LG
 ACCUMULATOR: 914mm O.D. x 2591mm LG
 STILL COLUMN: 356mm O.D. x 3353mm LG
 DESIGN PRESS.: 96 kPa
 500 000 BTU/HR

U-671 EXHAUST FAN
 120V/1Ø/60Hz

F-677A/B HARVARD FILTER
 E-672 EXCHANGER
 60-A5-213

OUT OF SERVICE

NOTES:
 THIS DRAWING IS OF A CONFIDENTIAL NATURE AND SHALL NOT BE REPRODUCED IN ANY MANNER, NOR USED FOR ANY PURPOSE WHATSOEVER EXCEPT BY WRITTEN PERMISSION OF CONCISE DESIGN.
 THIS DRAWING IS NOT APPROVED FOR CONSTRUCTION UNLESS SIGNED AND DATED. DESTROY ALL DRAWINGS BEARING EARLIER DATE AND/OR REVISION NUMBER.

No	DATE	REVISIONS	DRAWN	CHK.	APPD.
2	09-11-02	AS-BUILT (BY REDLINE)			
1	02-05-14	TRAIN #1/ TRAIN #3/ COMP. ADDITION - AS BUILT		A.M.	
0	01-11-07	ISSUED FOR CONSTRUCTION (854.06/07/08)		A.L.	
4	11-08-21	AS-BUILT (BY FLINT ENERGY)	JBR	DA	
3	08-04-2021	K-430 REPLACEMENT - ISSUED FOR CONSTRUCTION	D.A		



DRAWN: EB	Concise Design Engineering Services	
DATE: 01.07.23	300, 736 - 6 Avenue S.W. Calgary, Alberta T2P 3W1 Telephone: (403) 237-7160 Fax: (403) 237-7166	
CHK'D:	MURPHY OIL COMPANY LTD.	
APPR'VD:	LADYFERN b-17-1, 94-H-1 DEHYD PACKAGE No.8 (T-671) TRAIN #4 P & ID	
SCALE: NONE	CONCISE PROJ No. 01-854.06	CONCISE FILE No. 85463603
	CLIENT DWG. No. LDFb-171-220-25	CONCISE DWG. No. 01-854-3603
		REV. 4