



- NOTES:**
- 1) PIPING FOR HEATER COIL AND PIPING TO ADSORPTION TOWERS TO BE SA-335-P9.
 - 2) INDEPENDENT VENTING OUTSIDE THE BUILDING TO BE COMPLETED BY OTHERS AFTER BUILDING HAS BEEN ERRECTED AT SITE.
 - 3) REMOVABLE SPOOL FOR FUTURE INSTALLATION OF 2" CL. 900 RTJ ORBIT SWITCHING VALVE.
 - 4) VENT OUTSIDE DURING MAINTENANCE ONLY.
 - 5) LIFTING CAPABILITY, AND ACCESS, TO BE PROVIDED FOR SV-5042.
 - 6) VERTICAL PIPE SPOOL TO BE ADDED AT THE TAKEOFF FLANGE TO RAISE HM LINE TO COOLERS SO THAT FLARE PIPING MODIFICATIONS CAN BE COMPLETED.

E-5040
 GAS/GAS EXCHANGER
 10 3/4" OD x 9'-6" TS/TS
 1550 PSIG @ 650/-50°F MDMT
 SIZE TO BE CONFIRMED

V-5070
 REGENERATION GAS SEPARATOR
 16" OD x 5'-0" S/S
 1440 PSIG @ 650/-20°F MDMT

Equinox Engineering Ltd
ISSUED FOR
UN 0.5 2009
AS-BUILT
Document Control

DRAWING NO	REFERENCE DRAWINGS	REV	MOC NO. REVISION DESCRIPTION	BY	DATE	CHKD	APPD	BP APPD	ENGINEER'S STAMP	ENGINEERING RECORD
		A	ISSUED FOR APPROVAL	KH	2006-06-20	NOT ON ORIGINAL	NOT ON ORIGINAL	NOT ON ORIGINAL		DRAWN BY NOT ON ORIGINAL
		0	ISSUED FOR CONSTRUCTION	KH	2006-10-17	NOT ON ORIGINAL	NOT ON ORIGINAL	NOT ON ORIGINAL		DATE NOT ON ORIGINAL
		1	REVISED AS SHOWN	AEB	2006-12-20	NOT ON ORIGINAL	NOT ON ORIGINAL	NOT ON ORIGINAL		CHKD BY NOT ON ORIGINAL
		2	REVISED AS SHOWN	AEB	2007-07-06	NOT ON ORIGINAL	NOT ON ORIGINAL	NOT ON ORIGINAL		DATE NOT ON ORIGINAL
		3	AS BUILT	QF	2008-03-20	NOT ON ORIGINAL	NOT ON ORIGINAL	NOT ON ORIGINAL		ENGINEER NOT ON ORIGINAL
		4	MOC NO. 2006-3781 ISSUED FOR CONSTRUCTION	J. CORNELL	2008-08-19	J. CORNELL	CLAUDE MASSE	M ABOUGOUSH		
		5	MOC NO. 2006-3781 RE-ISSUED FOR CONSTRUCTION	A. DURAND	2008-10-07	J. CORNELL	CLAUDE MASSE	M ABOUGOUSH		
		6	MOC NO. 2006-3781 AS BUILT PER SITE VISIT	R. TERADO	2009-05-08	J. CORNELL	CLAUDE MASSE	M ABOUGOUSH		

BP Canada Energy Company
 CALGARY ALBERTA

AREA/PROJECT TWO LAKES

PREPARED BY PRESSON ENEFLEX

TITLE
LSD 06-03-63-13W6M
NARRAWAY TWO LAKES DEHYDRATION FACILITY
SOUR DESICCANT DEHYDRATION PACKAGE
PIPING AND INSTRUMENTATION DIAGRAM

SCALE NTS

EPCM DWG/PROJ NO. B7312-071 SHT. 3 OF 6

REV 6