



Mountain West Services Ltd.

Inspection Report - CNRL # 6904

[\[www.mtnwest.ca\]](http://www.mtnwest.ca) [\[Company Index Page\]](#) [\[Vessels\]](#) [\[Pipelines\]](#) [\[SMART\]](#) [\[Incidents\]](#) [\[Work Orders\]](#) [\[Management of Change\]](#)

194887- SEPARATOR

UT External

Province:	Alberta	Manway:	NO
District:	GPOU	Coating:	No
Location:	MONTNEY	Inspect Date:	10/17/2006
LSD:	11-33-073-09W6	Inspection Interval:	48
CRN:	F-6669.2	Next Inspection:	10/17/2010
Skid/Equipment Number:	SKID0211	MAWP:	1376 PSI 9487.2448 KPa
Service:	Sour	Temperature:	180 F 82.22 C
Status:	In Service	Outstanding NCRs:	0

General:

2006 Ultrasonic Corrosion Survey.

Safety Valves:

PSV [MWS64109](#) Protects the Shell Of the Vessel. Set Pressure of 1376 PSI / 9487.2448 KPa.
Capacity: 3605SCFM / 102.08m3/min

Status: In Service	Examination Methods: UT	Access: External	Cleaning: Good
---------------------------	--------------------------------	-------------------------	-----------------------

External:

Refer to 2006 VT External inspection report as part of this thorough inspection.

Internal:

The vessel was UT inspected for wall loss.

Hunt Inspections's Ultrasonic Corrosion Survey Project #C10093, as reported on Drawing #66, noted all vessel thickness readings to be above ASME Section VIII, Div. 1 code requirements at time of inspection. The calculated retirement date is 2026 with a program maximum of 20 years.

The associated piping was also inspected with no notable wall loss recorded.

Cautions were generated on 2" piping TML's 66-50, 66-55 and 66-60. Calculations indicate the areas are well above minimum required thickness for design conditions.
 The elbows appear to be at the low end of the 12.5% allowable mill undertolerance.
 Next inspection is 4 years or 1/2 remaining life, whichever is less.

Recommendations:

Recommend 4 year interval for next UT inspection.
 Ultrasonic Corrosion Survey due again in 2010.

Inspector's Declaration: I have witnessed the above inspections and certify that they have been done in accordance with our manual and that the information is accurate. I certify that the status of the pressure equipment detailed here is:

Suitable to be returned to service: Yes	Repairs complete: N/A
Repairs are still required: No	Suggested Inspection Interval: 48
Inspector: Duane Paetkau Cert #000087 Date: 2/13/2007	
Chief Inspector: I certify that the information on this report is true and that all inspections required by the Owner/User Quality Assurance Program# AQP-8047 which expires in 12/06/05 have been done.	
Chief Inspector: Jim Damiani Cert 00037 Date: 2/27/2007	

[\[Back To Start Page\]](#) [\[MtnWest.Ca\]](#)