

FORM U-1A MANUFACTURER'S DATA REPORT FOR PRESSURE VESSELS
(Alternative Form for Single Chamber, Completely Shop or Field Fabricated Vessels Only)
As Required by the Provisions of the ASME Code Rules, Section VIII, Division 1

1. Manufactured and certified by Petro Field Industries Inc. 3236 50th Ave S.E. Calgary Alberta T2B 3A3
(Name and address of Manufacturer)

2. Manufactured for Devon Canada Corp. 200 400 3 Ave. S.W. Calgary Alberta T2P 4H2
(Name and address of Purchaser) **(A)555783**

3. Location of installation STOCK
(Name and address)

4. Type VERTICAL C6-2448 T4890.2 CRN-24-1387-S-V-01 R0 N/A 2006
(Horiz. Or vert. tank) (Mfgs serial No.) (CRN) (Drawing No.) (Natl. Bd. No.) (Year built)

5. The chemical and physical properties of all parts meet the requirements of material specifications of the ASME BOILER AND PRESSURE VESSEL CODE. The design, construction, and workmanship conform to ASME Rules, Section VIII, Division 1 2004
Year

to 2005 N/A N/A
Addenda (Date) Code Case Nos. Special Service per UG-120(d)

6. Shell: SA516-70N 1.00" 0.125" 1'-10" 7'-6"
Matl. (Spec. No., Grade) Nom. Thk. (in.) Corr. Allow. (in.) Diam. I.D. (ft. & in.) Length (overall) (ft. & in.)

7. Seams: TYPE 1 FULL 100 1150 1 TYPE 1 FULL 100 1
Long. (Welded, Dbl., Sngl., Lap, Butt) R.T. (Spot or Full) Eff. (%) H.T. Temp. (°F) Time (hr) Girth (Welded, Dbl., Sngl., Lap, Butt) R.T. (Spot or Full) Eff. (%) No. of Courses

8. Heads: (a) Matl. SA516-70N 1150F/1Hr (b) Matl. SA516-70N 1150F/1Hr
(Spec. No., Grade) (Spec. No., Grade)

	Location (Top, Bottom, Ends)	Minimum Thickness	Corrosion Allowance	Crown Radius	Knuckle Radius	Elliptical Ratio	Conical Apex Angle	Hemispherical Radius	Flat Diameter	Side to Pressure (Convex or Concave)
(a)	Top/Bottom	0.9375"	0.125"			2:1				Concave
(b)										

If removable bolts used (describe other fastenings) N/A
(Matl., Spec. No., Gr., Size, No.)

9. MAWP 1387 N/A psi at max. temp. 167 N/A °F
(internal) (external) (internal) (external)

Min. design metal temp. -20 °F at 1387 psi. Hydro., pneu., or comb. test pressure Hydro 1803 psi.

10. Nozzles, inspection and safety valve openings:

Purpose (Inlet, Outlet, Drain)	No.	Diam. or Size	Type	Matl.	Nom. Thk.	Reinforcement Material	How Attached	Location
Inlet/Outlet/HLSD	3	3" 600cl	RFLWN	SA105N	0.81"	INTEGRAL	UW16.1(c)	Top Head/Shell
Drain	1	2" 600cl	RFLWN	SA106B/234WPB/105N	0.436"	INTEGRAL	UW16.1(c)	Bottom Head
Outlet/PSV	3	2" 600cl	RFLWN	SA105N	0.66"	INTEGRAL	UW16.1(c)	Shell
LCo.LCw.INSF	4	3" 600cl	RFLWN	SA105N	0.81	INTEGRAL	UW16.1(c)	Shell
LGo.LGo.TI.PI	6	3/4" 600cl	RFLWN	SA105N	0.57"	INTEGRAL	UW16.1(c)	Shell
SPARE	1	4" 600cl	RFLWN	SA105N	1.00"	INTEGRAL	UW16.1(c)	Shell
SPARE	2	3/4" 600cl	RFLWN	SA105N	0.57"	INTEGRAL	UW16.1(c)	Shell

11. Supports: Skirt Yes Lugs N/A Legs N/A Other N/A Attached Bottom Head- Welded
(Yes or No) (No.) (No.) (Describe) (Where and how)

12. Remarks: Manufacturer's Partial Data Reports properly identified and signed by Commissioned Inspectors have been furnished for the following items of the report: _____

(Name of part, item number, Mfg's. name and identifying stamp)

Vertical 3 Phase Separator. Construction Drawing C6-2448-VES-01R0, Impact Tests:No- UG-20(f)(1-5) and UCS-66(a)

Volume: 23.025 Cu. Ft. Full radiography per UW-11(a) and UW51.

Pressure relief device to be installed as per UG-125

CERTIFICATE OF SHOP/FIELD COMPLIANCE

We certify that the statements in this report are correct and that all details of design, material, construction, and workmanship of this vessel conform to the ASME Code for Pressure Vessels, Section VIII, Division 1. "U" Certificate of Authorization No. 35.571 expires January 19 2009

Date Sep. 18/06 Co. name Petro Field Industries Inc. Signed Farzad
(Manufacturer) (Representative)

CERTIFICATE OF SHOP/FIELD INSPECTION

Vessel constructed by Petro Field Industries Inc. at 3236 50th Ave S.E. Calgary Alberta T2B 3A3

I, the undersigned, holding a valid commission issued by the National Board of Boiler and Pressure Vessel Inspectors and/or the State or Province of Alberta and employed by ABSA have inspected

the pressure vessel described in this Manufacturer's Data Report on Sept 21/06, and state that, to the best of my knowledge and belief, the Manufacturer has constructed this pressure vessel in accordance with ASME Code, Section VIII, Division 1. By signing this certificate neither the Inspector nor his employer makes any warranty, expressed or implied, concerning the pressure vessel described in this Manufacturer's Data Report. Furthermore, neither the Inspector nor his employer shall be liable in any manner for any personal injury or property damage or a loss of any kind arising from or connected with this inspection.

Date 6/19/24 Signed [Signature] Commissions ex 115
(Authorized Inspector) (Natl Board (Incl. endorsements), State, Prov. and No.)