



Mountain West Services Ltd.

Inspection Report - CNRL # 9215

[\[www.mtnwest.ca\]](http://www.mtnwest.ca) [\[Company Index Page\]](#) [\[Vessels\]](#) [\[Pipelines\]](#) [\[SMART\]](#) [\[Incidents\]](#) [\[Work Orders\]](#) [\[Management of Change\]](#)

410656- SEPARATOR

UT External

Province:	Alberta	Manway:	NO
District:	GPOU	Coating:	No
Location:	TEEPEE CREEK FIELD	Inspect Date:	1/26/2008
LSD:	04-35-074-08W6	Inspection Interval:	48
CRN:	R-0138.123	Next Inspection:	1/26/2012
Skid/Equipment Number:	SKID0592	MAWP:	1440 PSI 9928.512 KPa
Service:	Sour	Temperature:	100 F 37.78 C
Status:	In Service	Outstanding NCRs:	0

General:

2008 Ultrasonic Corrosion Survey.

Safety Valves:

PSV [MWS68154](#) Protects the Shell Of the Vessel. Set Pressure of 1440 PSI / 9928.512 KPa.
Capacity: 22000SCFM / 622.97m3/min

Status: In Service	Examination Methods: UT	Access: External	Cleaning: Good
---------------------------	--------------------------------	-------------------------	-----------------------

External:

Refer to the latest VT External inspection report as part of this thorough inspection.

Internal:

The vessel was UT inspected for wall loss.

Hunt Inspections's Ultrasonic Corrosion Survey Project #C10175, as reported on Drawing #74, noted all vessel thickness readings to be above ASME Section VIII, Div. 1 code requirements at time of inspection. The calculated retirement date is 2028 with a program maximum of 20 years.
The associated piping was also inspected with no notable wall loss recorded.

Caution was generated on piping TML 74-35. Calculations indicate the area is well above minimum required thickness for design conditions.

The elbow appears to be at the low end of the 12.5% allowable mill undertolerance.

Next inspection is 4 years or 1/2 remaining life, whichever is less.

Recommendations:

Recommend 4 year interval for next UT inspection.

Ultrasonic Corrosion Survey due again in 2012.

Inspector's Declaration: I have witnessed the above inspections and certify that they have been done in accordance with our manual and that the information is accurate. I certify that the status of the pressure equipment detailed here is:

Suitable to be returned to service: Yes

Repairs complete: N/A

Repairs are still required: No

Suggested Inspection Interval: 48

Inspector: Duane Paetkau Cert #000087 **Date:** 4/7/2008

Chief Inspector: I certify that the information on this report is true and that all inspections required by the Owner/User Quality Assurance Program# AQP-9013 which expires in 12/11/2010 have been done.

Chief Inspector: Jim Damiani Cert 00037
Date: 4/14/2008

[\[Back To Start Page\]](#) [\[MtnWest.Ca\]](#)