



Mountain West Services Ltd.

Inspection Report - CNRL # 9361

[\[www.mtnwest.ca\]](http://www.mtnwest.ca) [\[Company Index Page\]](#) [\[Vessels\]](#) [\[Pipelines\]](#) [\[SMART\]](#) [\[Incidents\]](#) [\[Work Orders\]](#) [\[Management of Change\]](#)

414803- SEPARATOR

VT External

Province:	Alberta	Manway:	NO
District:	GPOU	Coating:	No
Location:	TEEPEE CREEK FIELD	Inspect Date:	2/8/2008
LSD:	12-25-074-08W6	Inspection Interval:	60
CRN:	L-8282.21	Next Inspection:	2/8/2013
Skid/Equipment Number:	SKID0595	MAWP:	1440 PSI 9928.512 KPa
Service:	Sour	Temperature:	130 F 54.44 C
Status:	In Service	Outstanding NCRs:	0

General:

Safety Valves:

PSV [MWS68158](#) Protects the Shell Of the Vessel. Set Pressure of 1415 PSI / 9756.142 KPa.
Capacity: 4871SCFM / 137.93m3/min

Status: In Service	Examination Methods: VT	Access: External	Cleaning: Good
---------------------------	--------------------------------	-------------------------	-----------------------

External:

All visible shell surfaces and nozzles appear in good condition. Name plate is intact and legible. Vessel supports, foundation, electrical bonding and external coating appear good. Associated piping, supports and components appear in good condition and alignment with no signs of leaks or defects present at the time of inspection. No evidence of short studding or nut rounding at time of inspection. Verify PSV protection and PSV's are properly installed with any block valves locked/sealed open. Verify vessel has A# and CRN stamping, PSV has correct code stamp and MWS tagging, and was last serviced within the required interval guidelines. Assign inspection interval.

Internal:

Recommendations:

Inspector's Declaration: I have witnessed the above inspections and certify that they have been done in accordance with our manual and that the information is accurate. I certify that the status of the pressure equipment detailed here is:	
Suitable to be returned to service: Yes	Repairs complete: N/A
Repairs are still required: No	Suggested Inspection Interval: 60
Inspector: Glenn Allen, MWS Date: 3/28/2008	
Chief Inspector: I certify that the information on this report is true and that all inspections required by the Owner/User Quality Assurance Program# AQP-9013 which expires in 12/11/2010 have been done.	
Chief Inspector: Jim Damiani Cert 00037 Date: 4/14/2008	

[\[Back To Start Page\]](#) [\[MtnWest.Ca\]](#)